

Bennington Fish Culture Station - Project Description

This project for the Vermont Fish and Wildlife Department is the second phase of construction to complete the water treatment facility /system at the Bennington Fish Culture Station. The project consisted of completing exterior water distribution piping, the floor drain discharge pipe system, interior plumbing, valves and piping, installation of water treatment equipment, monitoring, control and alarm systems, ventilation systems and electrical work. The project also included finish site work, paving, turf establishment and landscaping.



Setting the Ultraviolet Disinfection Units



The Rotary Drum Filters



Gate Valves on 12" PVC Water Supply Pipes